

CODE NARRATIVE - HAMPTON, VA- VA MEDICAL CENTER

BUILDING NAME	BUILDING 137C
BUILDNG OWNER	DEPARTMENT OF VETERANS AFFAIRS
STREET ADDRESS	
CITY	HAMPTON
STATE	VIRGINIA
ZIP CODE	
PROJECT CONSTRUCTION PURPOSE	ADDITION AND RENOVATION
CODES USED	NFPA 13, 2010 EDITION
	NFPA 72, 2010 EDITION
	NFPA 101, 2012 EDITION
	INTERNATIONAL BUILDING CODE, 2009 EDITION
	VA DESIGN MANUAL, 6 TH EDITION
DATE DEVELOPED	FEBRUARY 20, 2012
ARCHITECT INFORMATION	
COMPANY NAME	RDC/JOHN POE ARCHITECTS
STREET ADDRESS	524 FERNWOOD DRIVE
CITY, STATE, ZIP CODE	ALTOMONIE SPRINGS, FL
PHONE	937-461-3290
FAX	937-461-0260
CODE CONSULTANT	
COMPANY NAME	FP&C CONSULTANTS, INC.
STREET ADDRESS	1520 MAIN STREET
CITY, STATE, ZIP CODE	INDIANAPOLIS, INDIANA 46224
PHONE	317-486-5188
FAX	317-486-5189
EMAIL	INDY@FPC-CONSULTANTS.COM
OCCUPANCY GROUP	
1st FLOOR (RENOVATION/ADDITION)	I-2(IBC); HEALTH CARE (NFPA 101)
CONSTRUCTION TYPE	EXISTING BUILDING RESEMBLES TYPE II
	NEW ADDITION TYPE II
SINGLE STORY HEALTHCARE	ADDITION/RENOVATION
ACTUAL AREA PER FLOOR	
1 st FLOOR	40,000 sq. ft.
ALLOWABLE TOTAL AREA	
BASE	UL
FRONTAGE	NA
OCCUPANT LOADS	
1st FLOOR ADDITION	97
1st FLOOR RENOVATION	238
STRUCTURAL FRAME	0 HOUR REQUIRED, 0 HOUR PROVIDED
BEARING WALLS EXTERIOR	0 HOUR REQUIRED, 0 HOUR PROVIDED
BEARING WALLS INTERIOR	0 HOUR REQUIRED, 0 HOUR PROVIDED

NONBEARING WALLS EXTERIOR	NO RATING REQUIRED
NONBEARING WALLS INTERIOR	NO RATING REQUIRED
FLOORS AND FLOOR/CEILINGS	N/A
SHAFT ENCLOSURES	1 HOUR REQUIRED FOR SHAFTS THAT CONNECT LESS THAN 4 STORIES
STAIRWAY CONSTRUCTION	1 HOUR REQUIRED FOR SHAFTS THAT CONNECT LESS THAN 4 STORIES
AUTOMATIC SUPPRESSION SYSTEM	AUTOMATIC SPRINKLER SYSTEM REQUIRED, AUTOMATIC SPRINKLER SYSTEM PROVIDED
DETECTION & NOTIFICATION	FIRE ALARM SYSTEM REQUIRED, ADDRESSABLE SMOKE DETECTION INSTALLED, WAITING ROOMS & AREAS OPEN TO THE CORRIDOR, DUCT DETECTION INSTALLED THROUGHOUT, MANUAL PULL STATIONS AND SPRINKLER SYSTEM WATER FLOW AND TAMPER SWITCHES INSTALLED AS REQUIRED.
SMOKE EXHAUST SYSTEM	N/A
PORTABLE FIRE EXTINGUISHERS	FIRE EXTINGUISHER CABINETS ARE PROVIDED, FIRE EXTINGUISHERS ARE NOT PROVIDED AS PART OF THIS CONTRACT.
EMERGENCY LIGHTING AND POWER SYSTEMS	REQUIRED IN THE MEANS OF EGRESS, ILLUMINATED EXIT SIGNS PROVIDED WITH A 90 MINUTE EMERGENCY POWER BATTERY BACKUP
EGRESS	THE MEANS OF EGRESS SHALL REMAIN CLEAR AND FREE OF DEBRIS DURING DEMOLITION AND CONSTRUCTION. THE EXIT, EXIT ACCESS, AND EXIT DISCHARGE SHALL BE ACCESSIBLE TO ALL OCCUPANTS AT ALL TIMES
	ALL EXITS, TEMPORARY OR PERMANENT, SHALL BE MARKED WITH THE APPROPRIATE ILLUMINATED DIRECTIONAL EXIT SIGN AND BE CLEARLY IDENTIFIABLE IN ALL EXIT PASSAGEWAYS, PHOTOLUMNESCIENCE EXIT SIGNS SHALL NOT BE USED.
	PASSAGEWAYS OR DOORS THAT DO NOT SERVE, OR CONNECT TO AN EXIT PASSAGEWAY SHALL BE CLEARLY MARKED WITH A "NO EXIT" SIGN
KITCHEN	UL LISTED HOOD PROVIDED PER MECHANICAL DRAWINGS

SYMBOLS LIST

OF TRAVEL)

COMMON PATH (feet) FIRE EXTINGUISHER

OCCUPANT LOAD

HE HORIZONTAL EXIT PASSAGEWAY

EGRESS WIDTH (feet) EXIT CAPACITY (persons)(actual/capacity)

EX EXIT AREA OPEN TO CORRIDOR NO SMOKE DETECTION REQUIRED

IIIIIII 0-HR SMOKE PARTITION - NFPA 101-8.4

■ I ■ I ■ I ■ I 1-HR SMOKE BARRIER - NFPA 101-8.5

■ ■ ■ 1-HR FIRE BARRIER - NFPA 101-8.3

2-HR FIRE BARRIER - NFPA 101-8.3

EXISTING BUILDING - NO NEW WORK

EXISTING BUILDING - AREA OF RECONSTRUCTION


NEW CONSTRUCTION/ADDITION

CODE PLAN - FIRST FLOOR

Scale: 1" = 20'-0"

CONSULTANTS: FIRE PROTECTION & CODE CONSULTANTS

FP&C CONSULTANTS, INC. 1520 MAIN STREET INDIANAPOLIS, IN 46224 (317)486-5188



Hampton VA, VAMC Renovate / Expand SCI, Phase II, 590-911 CODE DATA ||Checked | TH Building Number 137

04/26/2013 590-911 RDC/JPA Project No. 11004.00 137-G001


one-eighth inch = one foot

Proj. # 1907.00


Drawing Title

Approved: Project Director

Hampton, Va



Hampton, Va jpa@johnpoe.com . 10 of 135



N Deduct Alt First Floor
Scale: 1/16" = 1'-0"

ARCHITECT/ENGINEERS: RDC/JOHN POE ARCHITECTS 524 FERNWOOD DRIVE ALTAMONTE SPRINGS, FLORIDA 937 461 3290 PHONE 937 461 0260 FAX 1-800-362-1523 jpa@johnpoe.com

DEDUCT ALTERNATES

Hampton VA, VAMC Renovate / Expand SCI, Phase II, 590-911 05/03/2013 590-911 RDC/JPA Project No. 11004.00 137

○ DEDUCT ALTERNATES NOTES

indicated in the contract documents.

scope of work.

documents.

A BID ITEM 1 (BASE BID); Contractor shall perform all work as indicated in the contract documents including general construction, alterations, roads, walks, grading, drainage, mechanical and electrical work, utility systems, necessary removal of existing structures and construction and certain other items.

1 Deduct Alternate 1: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all Architectural and Electrical work associated with the electric shades at the bedroom windows, including power and connection to patient controls as

2 Deduct Alternate 2: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2 and deduct all Civil and Electrical work associated with the parking lot, including emergency blue light/phone, CCTV camera, adjustments to sidewalks, etc. on the east side of Franklin Street as indicated in the contract documents. Detention/retention pond street lighting standards, concrete base, pull boxes, circuitry, conduit and CCTV/Emergency Phone cabling/power to remain in

3 Deduct Alternate 3: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, and deduct all Structural work associated with repairs to the existing concrete slab/pan joist/beam floor system in the existing Building 137C as indicated in the contract

4 Deduct Alternate 4: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with

BID ITEM 2, BID ITEM 3, BID ITEM 4, and deduct all Civil, Architectural, and Electrical work associated with courtyard fit out including concrete sidewalks, site lighting, pergola, planting beds,

5 Deduct Alternate 5: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, BID ITEM 4, BID ITEM 5, and deduct all Architectural and Plumbing, Mechanical, Electrical and Fire Protection systems work associated with resident kitchen/warming

6 Deduct Alternate 6: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, BID ITEM 4, BID ITEM 5, BID ITEM 6, and deduct/revise interior Architectural finishes and Plumbing, Mechanical, and Electrical systems at the four bed (west) addition as indicated in the contract documents, except those finishes and

systems necessary to complete Corridor 1C13 and stairs

1C203/1C204. Construct alternate plans for rooms C127, C127A, C129, C129A, C123A, C132B, C133, C133A, C134 and C134A as indicated in the contract documents as part of this BID ITEM. 7 Deduct Alternate 7: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, BID ITEM 4, BID ITEM 5, BID ITEM 6, BID ITEM 7, and deduct the balance of Civil, Architectural,

Structural and Plumbing, Mechanical, Electrical and Fire Protection systems work associated with the four bed (west) addition shell as

lighting as indicated in the contract documents. New items that are part of other systems such as fire alarm devices, nurse call lights, etc. are to remain in project scope. Patching of finishes at new wall openings will match existing materials as closely as possible. New doors and existing door slabs being replaced will remain in the

8 Deduct Alternate 8: Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, BID ITEM 4, BID ITEM 5, BID ITEM 6, BID ITEM 7, BID ITEM 8, and deduct new Architectural finish materials in the existing building corridors, including soffits, ceilings, wall finishes, wall protection, base and flooring and new corridor

etc as indicated in the contract documents.

kitchen as indicated in the contract documents.

indicated in the contract documents.

137-G003 g. **11** of **135**

8 9


JOHN A. POE Lic. No. 015768

Date

CONSULTANTS:

Drawing Title

Approved: Project Director



Date

1-800-362-1523

jpa@johnpoe.com

Hampton, Va

. 12 of 135

